

FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FERAZPUR											
TYPE 5 RESIDENCE											
S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
ALL FLOORS											
1	Main Entrance Steps	Acid Wash Granite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.
2	Main Entrance ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.
3	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-
4	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-
5	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	150mm high skirting same as flooring + 900 mm high enamel paint	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	SS RAILING AS/ SPEC.
RESIDENTIAL UNIT											
6	Living Area	18mm th prepolished granite of approved shade /600x600mm rectivied tiles/scratch resistant engineered wood/laminated flooring	150mm high 18mm th prepolished granite of approved shade /600x600mm rectivied tiles/scratch resistant engineered wood/laminated flooring	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-
7	Dining Area	18mm th prepolished granite of approved shade /600x600mm rectivied tiles/scratch resistant engineered wood/laminated flooring	150mm high 18mm th prepolished granite of approved shade /600x600mm rectivied tiles/scratch resistant engineered wood/laminated flooring	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-
8	Kitchen	600x600 mm antiskid Rectified Vitrified Tile with water absorbtion less than 0.08% with joints finished with nmatching grout Double Charged	150 mm higg Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Polished Granite	-	-	-	-
9	Master Bedroom	18mm th prepolished granite of approved shade /600x600mm rectivied tiles/scratch resistant engineered wood/laminated flooring	150mm high 18mm th prepolished granite of approved shade /600x600mm rectivied tiles/scratch resistant engineered wood/laminated flooring	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-
10	Bedroom	18mm th prepolished granite of approved shade /600x600mm rectivied tiles/scratch resistant engineered wood/laminated flooring	150mm high 18mm th prepolished granite of approved shade /600x600mm rectivied tiles/scratch resistant engineered wood/laminated flooring	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-
11	Toilets	600x600 mm Rectified Vitrified Tile Double Charged	150 mm higg Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Polished Granite	-	-	-	-
12	Servant Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm higg Rectified Vitrified Tile	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
13	Balcony/ Verandah	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	painted (including necessary lipping)Other door : 35mm thick factory made flush door shutters both side commercial ply veneering and finished with wooden Putty and painted.W.C Bath Room : 30mm thick factory made flush door shutters one side commercial ply veneering and finished with wooden Putty & painted and 1 mm thick laminate from insideNote Synthetic enamel paint on all wood works and steel works.			SS RAILING AS/ SPEC.
14	Utility Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.
15	Box Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm higgh Rectified Vitrified Tile	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				-

FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FEROPUR

TYPE 4 RESIDENCE

S.n o.	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	DOOR FRAME	DOOR	WINDOW	COUNTER	RAILING	
ALL FLOORS												
1	Main Entrance Steps	Acid Wash Granite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.	
2	Main Entrance ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.	
3	Corridor	18mm th prepolished granite of approved shade /600x600mm rectified tiles/scratch resistant engineered wood/laminated flooring	150mm high 18mm th prepolished granite of approved shade /600x600mm rectified tiles/scratch resistant engineered wood/laminated flooring	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-	
4	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	-	
5	Staircase	18mm Polished single pelce Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	150mm high skirting same as flooring + 900 mm high enamel paint	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	SS RAILING AS/ SPEC.	
RESIDENTIAL UNIT												
6	Living Area	18mm th prepolished granite of approved shade /600x600mm rectified tiles/scratch resistant engineered wood/laminated flooring	150mm high 18mm th prepolished granite of approved shade /600x600mm rectified tiles/scratch resistant engineered wood/laminated flooring	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	<p>Frames : chemical treated Hard wood. The external entrance door frame will have double rebate i.e. main door and safety grill door with SS 304 wire (Power Coated) mesh. For internal doors single rebate frames compatible to door shutter.Main door Shutter: Double shutter one safety grill single/ double leaf door in SS 304 L grade frame with mosquito proof stainless steel proof stainless steel wire-mesh of stainless steel-304 grade (Power coated) and stainless fittings and other with 35mm thick factory made exterior grade both side decorative veneered type flush door shutter with melamine polish (including necessary lipping)Other door : 35mm thick factory made exterior grade both side decorative veneered type flush door shutter with melamine polish.W.C Bath Room : 30mm thick chemically treated hardwood/UPVC extruded frame section with wall thickness of 1.7 mm / FRP/ PVC compatible to shutters servant roomFrames : chemical treated Hard wood. The external entrance door frame will have double rebate i.e. main door and safety grill door with SS 304 wire (Power Coated) mesh. For internal doors single rebate frames compatible to door shutter.Main door Shutter: Double shutter one mid steel (Hot Dip Galvanized) grill door with mosquito proof stainless steel wire mesh of SS-304 grade (Power Coated), painted and other 35 mm thick factory made flush door shutter both side commercial veneered and painted (including necessary lipping)Other door : 35mm thick factory made flush door shutters both side commercial ply veneering and finished with wooden Putty and painted.W.C Bath Room : 30mm thick factory made flush door shutters one side commercial ply veneering and finished with wooden Putty & painted and 1 mm thick laminate from insideNote Synthetic enamel paint on all wood works and steel works.</p>	-	-	-		
7	Dining Area	18mm th prepolished granite of approved shade /600x600mm rectified tiles/scratch resistant engineered wood/laminated flooring	150mm high 18mm th prepolished granite of approved shade /600x600mm rectified tiles/scratch resistant engineered wood/laminated flooring	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.		-	-	-	-	
8	Kitchen	600x600 mm antikid Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.		-	-	-	Kitchen Cooking platform top in pre-polished granite stone	
9	Bedroom	18mm th prepolished granite of approved shade /600x600mm rectified tiles/scratch resistant engineered wood/laminated flooring	150mm high 18mm th prepolished granite of approved shade /600x600mm rectified tiles/scratch resistant engineered wood/laminated flooring	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.		-	-	-	-	Frames : Chemically treated hard wood / UPVC excluded frame section with minimum wall thickness of 1.7 mm Shutter: UPVC extruded profiles of min wall thickness of 1.7 mm /30mm thick second class teak wood with glazing of float glass
10	Toilets	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.		-	-	-	Polished Granite	
11	Servant Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.		-	-	-	-	
12	Balcony/ Verandah	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.		-	-	-	-	SS RAILING AS/ SPEC.
13	Utility Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.		-	-	-	-	SS RAILING AS/ SPEC.

FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FEROPUR											
TYPE 3 RESIDENCE											
S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
ALL FLOORS											
1	Main Entrance Steps	Acid Wash Granite	-	-	-	-	-				SS RAILING AS/ SPEC.
2	Main Entrance ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-				SS RAILING AS/ SPEC.
3	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				-
4	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				-
5	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	150mm high skirting same as flooring + 900 mm high enamel paint	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.
RESIDENTIAL UNIT											
6	Living Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				-
7	Dining Area	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				-
8	Kitchen	600x600 mm antiskid Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Kitchen Cooking platform top in pre-polished granite stone				-
9	Bedrooms	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				-
10	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Polished Granite				-
11	Verandah/Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.
12	Utility Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Plastic Emulsion paint of low VOC upto ceiling bottom over 6mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 6mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.

Frames : chemical treated Hard wood. The external entrance door frame will have double rebate i.e. main door and safety grill door with SS 304 wire (Power Coated) mesh. For internal doors single rebate frames compatible to door shutter.
Main door Shutter: Double shutter one mild steel (Hot Dip Galvanized) grill door with mosquito proof stainless steel wire mesh of SS-304 grade (Power Coated), painted and other 35 mm thick factory made flush door shutter both side commercial veneered and painted (including necessary lipping)
Other door : 35mm thick factory made flush door shutters both side commercial ply veneering and finished with wooden Putty and painted.
W.C Bath Room : 30mm thick factory made flush door shutters one side commercial ply veneering and finished with wooden Putty & painted and 1 mm thick laminate from inside
Note: Synthetic enamel paint on all wood works and steel works.

Frames : Power coated or colour anodized aluminium extruded tubular sections having double rebate for glazed and wire mesh shutters along with the provision of sub frame of suitable material. Shutters : Double shutter one glazed shutters with frames of /powder coated or colour anodized aluminium extruded tubular sections with glazing of float/ toughened glass as per design & requirement and other shutter with stainless steel SS-304 grade wire-mesh in place of glazing.

FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FEROPUR											
BACHELOR DR. HOSTEL											
S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
GROUND FLOOR											
1	Entrance Ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.
2	Entrance Steps	Acid Wash Granite									SS RAILING AS/ SPEC.
3	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
4	Staircase	18mm Polished singgle peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-			Powder coated extruded Aluminium double rebate frame with M S Enamel paintedGrill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
5	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel paintedGrill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
6	Entrance Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
7	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
8	Office	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
9	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
9	Dining Area	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
10	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	Kitchen Cooking platform top in pre-polished granite stone	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
27	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
10	Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
11	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
12	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Kitchen Cooking platform top in pre-polished granite stone			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
13	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.
FIRST FLOOR											

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
27	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
28	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
29	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
30	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
31	Caretaker Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
32	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
33	Recreation Room	3 mm thick Vinyl flooring with seamless joint on self levelled base of CC	150mm high 3mm thick Seamless Vinyl	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
35	Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
36	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
37	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Kitchen Cooking platform top in pre-polished granite stone			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
38	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.
SECOND FLOOR											
53	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
54	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
55	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
56	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
60	Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
61	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame(from Forest Stewardship Council approved vendor)(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	-	-
62	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Kitchen Cooking platform top in pre-polished granite stone	-	-	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
63	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	SS RAILING AS/ SPEC.
THIRD FLOOR											
79	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	-	-	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
80	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame	-	-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
81	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
82	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
84	Laundry	600x600 mm Rectified Vitrified Tile Double Charged	150 mm highh Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
85	Gym	3 mm thick Vinyl flooring with seamless joint on self levelled base of CC	150mm high 3mm thick Seamless Vinyl	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
86	Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm highh Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
87	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm highh Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
88	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Kitchen Cooking platform top in pre-polished granite stone			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
89	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.
FOURTH FLOOR											
106	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
107	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
108	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
109	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
110	Living Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
111	Bedroom	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
112	Dining	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
	Dress	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	12.5 mm Double Layer Gypsum Board with trap door	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Kitchen Cooking platform top in pre-polished granite stone			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
113	Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
114	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
115	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Kitchen Cooking platform top in pre-polished granite stone			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
116	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.
FIFTH TO NINTH FLOOR											
132	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
133	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
134	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted/Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
135	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
136	Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted/Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
137	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	teak wood frame(from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
138	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	Kitchen Cooking platform top in pre-polished granite stone			Powder coated extruded Aluminium double rebate frame with M S Enamel painted/Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
139	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.

FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FEROPUR

GUEST HOUSE

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
GROUND FLOOR											
1	Entrance Ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.
2	Entrance Steps	Acid Wash Granite									SS RAILING AS/ SPEC.
3	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
4	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
5	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
6	Entrance Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
7	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
8	Office	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
9	Dining Area	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border		Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
10	Kitchen	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm ceramic glazed tile from floor to full height	-	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	Kitchen Cooking platform top in pre-polished granite stone	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
11	Bed Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
12	Dress	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	12.5 mm Double Layer Gypsum Board with trap door	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
13	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	-	-
14	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	-	SS RAILING AS/ SPEC.
FIRST FLOOR											
1	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame	-	-
2	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
3	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
4	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
5	Store	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
6	Gym	3 mm thick Vinyl flooring with seamless joint on self levelled base of CC	150mm high 3mm thick Seamless Vinyl	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
7	Bed Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
9	Dress	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	12.5 mm Double Layer Gypsum Board with trap door	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
9	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
10	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
SECOND FLOOR											
1	Lift Lobby	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	Pre polished granite cladding upto ceiling on one wall having doors of lift. Rest of the walls will be 150mm high skirting same as flooring.	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
2	Staircase	18mm Polished single peice Granite slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	900 mm high enamel paint + 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper upto ceiling	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-			Powder coated extruded Aluminium double rebate frame with M S Enamel paintedGrill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
3	Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	150mm skirting same as floor +Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-			Powder coated extruded Aluminium double rebate frame with M S Enamel paintedGrill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
4	Electrical Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	2 hrs Fire Rated M.S Powder Coated Frame	2 hrs Fire Rated M.S Powder Coated Frame		-
5	Store	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
6	Bed Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel paintedGrill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
7	Dress	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	12.5 mm Double Layer Gypsum Board with trap door	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
8	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic glazed/ vitrified Tiles Dado from floor to full height	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling	-	Teak wood frame (from Forest Stewardship Council approved vendor)	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
9	Balcony	600x600 mm Rectified Vitrified Tile Double Charged	150mm high skirting with stone coping	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-				SS RAILING AS/ SPEC.

FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FEROPUR

MORTUARY

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
1	Entrance Ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.
2	Entrance Steps	Acid Wash Granite									SS RAILING AS/ SPEC.
3	Lobby/ Corridor	18mm Polished Granite in larger slabs in one or more colours as per design	150mm high 18mm Polished Granite	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partical board		-
4	Office for Police	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border		Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partical board		
5	Post Mortem Hall	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	900mm 300x450mm ceramic tile + stone beading	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partical board		-
6	Student Gallery	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border		Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partical board		-
7	Body Store	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partical board		-
8	Sanitation Staff	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border		Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partical board		-

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
9	Store Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
10	Sluice Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	-	Powder coated extruded Aluminium	Both side laminated 35 mm thick Flush Door (1mm+35mm +1mm)		-
11	In-Charge Office	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border		Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partial board		-
12	Toilet Male	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic Tiles Dado upto 100mm above false ceiling	-	600 x 600 GI Powder Coated Metal False Ceiling	-	Powder Coated Aluminium Frame (with Hardwood Insert)	Painted Flush Door Shutter (thickness 35 mm)		-
13	Toilet Female	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic Tiles Dado upto 100mm above false ceiling	-	600 x 600 GI Powder Coated Metal False Ceiling	-	Powder Coated Aluminium Frame (with Hardwood Insert)	Painted Flush Door Shutter (thickness 35 mm)		-
14	Phy. Disable Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	300x450mm Ceramic Tiles Dado upto 100mm above false ceiling	-	600 x 600 GI Powder Coated Metal False Ceiling	-	Powder Coated Aluminium Frame (with Hardwood Insert)	Painted Flush Door Shutter (thickness 35 mm)		

**FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FEROZPUR
MANIFOLD & PLANT ROOM AND KITCHEN**

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
GROUND FLOOR											
1	Entrance Ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-				SS RAILING AS/ SPEC.
2	Entrance Steps	Acid Wash Granite									SS RAILING AS/ SPEC.
3	MGPS Plant Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	M S Rolling Shutter (With Mechanical Device)	Powder Coated Aluminium Frame with Fully glazed DGU glass as per specs Aluminium Shutter with 19 mm thk Granite Stone Sill	-
4	Central Kitchen	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	ceramic tile upto 100mm above false ceiling	-	600 x 600 GI Powder Coated Metal False Ceiling with Gypsum Border	Kitchen Cooking platform top in pre-polished granite stone	Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated parical board	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
5	Toilets	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	Ceramic Tiles Dado upto 100mm above false ceiling	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated parical board		-

FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FEROPUR

WASTE MANAGEMENT BLOCK

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
1	Entrance Ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.
2	Operator Room	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
3	Sterilizer Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	M S Rolling Shutter (With Mechanical Device)	-	SS RAILING AS/ SPEC.
4	Organic Waste	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	M S Rolling Shutter (With Mechanical Device)	-	-
5	Non-Organic Waste	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	M S Rolling Shutter (With Mechanical Device)	-	-
6	Bio-Medical Waste	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	M S Rolling Shutter (With Mechanical Device)	-	-
7	Corridor	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	M S Rolling Shutter (With Mechanical Device)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-

FINISHING SCHEDULE FOR PROPOSED PGI SATELLITE CENTER AT FEROPUR

ELECTRIC SUB STATION

S.no	LOCATION	FLOORING	SKIRTING	DADO	WALL FINISH	CEILING/FALSE CEILING	COUNTER	DOOR FRAME	DOOR	WINDOW	RAILING
1	Entrance Ramp	25mm thick CC chequered Tiles in size 300 mm x 300 mm with Cement concrete flooring with hardonite	-	-	-	-	-	-	-	-	SS RAILING AS/ SPEC.
3	LT Panel Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	M S Rolling Shutter (With Mechanical Device)	-	-
4	HT Panel Room	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	M S Rolling Shutter (With Mechanical Device)	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	SS RAILING AS/ SPEC.
5	Office	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	-	-	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
6	Store	Kota Stone flooring (Size 550mm x 550mm) (mirror polished in internal area and normal polished in other areas) with 10-15% White/Green Marble.	150mm high polished Kota Stone	-	Acrylic Emulsion paint of low VOC upto ceiling bottom over 2mm thick POP	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partial board	Powder coated extruded Aluminium double rebate frame with M S Enamel painted Grill one shutter fully glazed float glass as per specs and one with SS wire mesh powder coated Extruded Aluminium shutter	-
7	Toilet	600x600 mm Rectified Vitrified Tile Double Charged	150 mm high Rectified Vitrified Tile	Ceramic Tiles Dado upto 100mm above false ceiling	-	6mm thk cement plaster finished with cement putty + ceiling to be treated with 2mm thick POP (one time only) and painted with low VOC acrylic washable distemper.	-	Powder coated extruded Aluminium	Partially glazed laminated panelled Powder Coated Aluminium door with 6mm thick fixed glass at top and 12mm thick both side laminated partial board	-	-